

PAVING IMPROVEMENTS FOR WEST BROAD STREET LEFT TURN LANE AND DRIVEWAY											
BID COMPARISONS											
Item No.	Quantity		Description & Price In Words	Rebecon, Inc.		McClendon Construction Co., Inc.		GRod Construction,LLC		KenDo Contracting	
	No.	Unit		Unit Price	Total	Unit Price	Total	Unit Price	Toatal	Unit Price	Toatal
1A	1	LS	Mobilization & Bonds, complete and executed, for the sum of Dollars and Cents per Lump Sum	\$ 18,000.00	\$ 18,000.00	\$ 7,500.00	\$ 7,500.00	\$ 25,500.00	\$ 24,500.00	Disqualify	Disqualify
2A	1	LS	Provide Construction Storm Water Pollution Prevention Management, including but not limited to, inlet protection, dust control and sweeping during construction, work fully performed for the sum of: Dollars and Cents per Lump Sum	\$ 2,000.00	\$ 2,000.00	\$ 4,550.00	\$ 4,550.00	\$ 5,500.00	\$ 5,500.00	Disqualify	Disqualify
3A	1	LS	Furnish and Install Traffic Control Devices such as striping, pavement markings and buttons, complete and in place for the sum of Dollars and Cents per Square Foot	\$ 20,000.00	\$ 20,000.00	\$ 9,250.00	\$ 9,250.00	\$ 13,500.00	\$ 13,500.00	Disqualify	Disqualify
4A	1491	SF	Demolition of median at the dimensions and location shown on the plans for the proposed Left Turn Lane to serve 1197 W. Broad Street, including saw cutting full depth, removal, and proper disposal of existing pavement for the sum of Dollars and Cents per Lump Sum	\$ 15.00	\$ 22,365.00	\$ 4.00	\$ 5,964.00	\$ 7.00	\$ 10,437.00	Disqualify	Disqualify
5A	1	LS	Remove and properly dispose of trees and crape myrtles for the sum of Dollars and Cents peLump Sum	\$ 2,100.00	\$ 2,100.00	\$ 3,000.00	\$ 3,000.00	\$ 1,250.00	\$ 1,250.00	Disqualify	Disqualify
6A	1	LS	Relocation and adjustment of existing utilities, including but not limited to, relocation of existing light pole(s), removing and plugging of existing sprinkler control valves, and valve boxes, adjustment to finished grade of existing valves, complete and in place for the sum of Dollars and Cents per Lump Sum	\$ 10,040.00	\$ 10,040.00	\$ 16,950.00	\$ 16,950.00	\$ 8,100.00	\$ 8,100.00	Disqualify	Disqualify
7A	228	LF	Installation of 228 linear feet of 6" & 4" specified conduits and two (2) pull boxes, complete and in place for the sum of Dollars and Cents per Linear Foot	\$ 60.00	\$ 13,680.00	\$ 50.00	\$ 11,400.00	\$ 29.00	\$ 6,612.00	Disqualify	Disqualify
8A	408	SF	Remove, Salvage, and reinstall existing pavers in median at the dimensions and location shown on the plans for the proposed left turn lane to serve 1197 W. Broad Street, complete and in place for the sum of Dollars and Cents per Square foot	\$ 19.00	\$ 7,752.00	\$ 15.00	\$ 6,120.00	\$ 13.00	\$ 5,304.00	Disqualify	Disqualify
9A	3328	SF	Lime stabilized subgrade (12" cement treated subgrade may be used in lieu of lime stabilization), complete and in place for the sum of Dollars and Cents per Square foo	\$ 3.00	\$ 9,984.00	\$ 3.50	\$ 11,648.00	\$ 4.50	\$ 14,976.00	Disqualify	Disqualify
10A	2902	SF	Furnish & Install 9-inch thick Portland Cement Concrete for Left Turn Lane to serve 1197 W. Broad Street, consistent with City of Mansfield details, including reinforcement, joints, complete and in place for the sum of Dollars and Cents per Square foot	\$ 17.00	\$ 49,334.00	\$ 16.00	\$ 46,432.00	\$ 10.50	\$ 30,471.00	Disqualify	Disqualify
11A	1264	SF	Furnish additional pavers identical to existing pavers as needed, and install pavers consistent with the City of Mansfield details, complete and in place for the sum of Dollars and Cents per Square foot	\$ 10.00	\$ 12,640.00	\$ 16.00	\$ 20,224.00	\$ 17.50	\$ 22,120.00	Disqualify	Disqualify
A) Total Bid for Left Turn Lane					\$ 167,895.00		\$ 143,038.00		\$ 142,770.00	Disqualify	Disqualify

PAVING IMPROVEMENTS FOR WEST BROAD STREET LEFT TURN LANE AND DRIVEWAY											
BID COMPARISONS											
Item No.	Quantity		Description & Price In Words	Rebecon, Inc.		McClendon Construction Co., Inc.		GRod Construction,LLC		KenDo Contracting	
	No.	Unit		Unit Price	Total	Unit Price	Total	Unit Price	Toatal	Unit Price	Toatal
1B	1536	SF	Demolition of existing driveway located at 1188 W. Broad Street, including saw cutting full depth, removal, and proper disposal of existing pavement to limits shown, complete and in place for the sum of Dollars and Cents per Square foot	\$ 5.00	\$ 7,680.00	\$ 4.00	\$ 6,144.00	\$ 2.00	\$ 3,072.00	Disqualify	Disqualify
2B	1078	SF	Furnish & Install 8-inch thick Portland Cement Commercial Concrete Driveway, consistent with City of Mansfield Commercial Drive Approach details, at 1188 W. Broad Street, over native soil compacted to 95% ASTM D698, at Optimum Moisture Content or above, including all the reinforcement and joints, complete and in place for the sum of Dollars and Cents per Square foot	\$ 14.00	\$ 15,092.00	\$ 15.00	\$ 16,170.00	\$ 10.50	\$ 11,319.00	Disqualify	Disqualify
3B	224	SF	Furnish & Install four-inch (4") thick, six-foot (6') wide Concrete Sidewalk along the frontage of 1188 W. Broad Street at the modified Commercial Driveway, including reinforcement and joints, complete and in place for the sum of Dollars and Cents per Square foot	\$ 17.00	\$ 3,808.00	\$ 9.00	\$ 2,016.00	\$ 6.00	\$ 1,344.00	Disqualify	Disqualify
4B	2	EA	Furnish and install "Do Not Enter" signs consistent with City of Mansfield Standards, complete and in place for the sum of Dollars and Cents per Each	\$ 500.00	\$ 1,000.00	\$ 500.00	\$ 1,000.00	\$ 450.00	\$ 900.00	Disqualify	Disqualify
5B	1	LS	Furnish and Install Traffic Control Devices, such as striping and pavement markings, complete and in place for the sum of Dollars and Cents per Lump Sum	\$ 2,000.00	\$ 2,000.00	\$ 650.00	\$ 650.00	\$ 1,800.00	\$ 1,800.00	Disqualify	Disqualify
B) Toatal Bid for Driveway					\$ 29,580.00		\$ 25,980.00		\$ 18,435.00	Disqualify	Disqualify
TOTAL BID					\$ 197,475.00		\$ 169,018.00		\$ 161,205.00	Disqualify	Disqualify